


NOTE:
CORE DRILL (E) CONCRETE SEWER WALL TO PROVIDE OPENING 6" LARGER THAN OD OF (N) 12" DIP SEWER. ROUGHEN SURFACE TO 1/4" AMPLITUDE. INSERT (N) 12" DIP, PLACE 2-#4 HOOPS AROUND (N) 12" DIP AND PACK ANNULAR SPACE WITH NON-SHRINK GROUT. BEND ALL (E) REBARS IF ENCOUNTERED TO HOOPS, AND CLEAN SURFACE. (N) DIP SHALL BE FLUSH W/ INSIDE FACE OF SEWER WALL.



ELEVATION DATUM SFVD13
SEWER SIZED BY B.A.
APPROVED BY B.S.

NO.	DATE	DESCRIPTION	BY	APP.
1	12/17	RFI #007	TW	LW
2	10/16	ISSUED FOR BIDS	AS	LW

TABLE OF REVISIONS

REFERENCE INFORMATION & FILE NO. OF SURVEYS
44,572
41,274
285
BK-055_PG-035
SH-18-160
41,280



DESIGN & ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 • 6028

Section Mgr:	LESLEY WONG	Date:	
Deputy Division Mgr:	IQBAL DHAPA	DESIGNED:	DATE: J.K./A.S. 11/2016
Division Mgr:	PATRICK RIVERA	DRAWN:	DATE: A.KIRSCH 11/2016
		CHECKED:	DATE: G.FONG 11/2016



SCALE: AS NOTED
SHEET OF SHEETS

2ND STREET STREETSCAPE IMPROVEMENTS PROJECT
2ND STREET SEWER REPLACEMENT STATION 46+00 TO 50+00
PLAN, PROFILE AND DETAIL

CONTRACT NO. 1064J
DRAWING NO. SW-10
FILE NO. 106,252
REV. NO. 1